

# Woolgoolga to Wells Crossing

Upgrading the Pacific Highway

**CONCEPT DESIGN REPORT**

**APRIL 2008**



---

Roads and Traffic Authority  
**SH10 Pacific Highway**  
**Woolgoolga to Wells Crossing**

Concept Design Report

April 2008

RTA/Pub. 08.087A

ISBN 978-1-921242-35-9

---

# Contents

Executive summary	i
<b>1. Introduction</b>	<b>1</b>
1.1 Project boundaries	1
1.2 Project definition	5
1.3 Highway upgrade scenarios	5
1.4 Overview of the project methodology	6
1.5 Project objectives	6
1.6 Purpose and scope	7
1.7 Drawing content	7
1.8 Report content	8
1.9 Specialist investigations	9
<b>2. Highway corridor</b>	<b>10</b>
2.1 Project limit of works	10
2.2 Project sections	10
2.3 Selection of the preferred route	13
2.4 Summary of the preferred route	20
<b>3. Arterial and motorway standard access strategies</b>	<b>21</b>
3.1 Description of the highway alignment	21
3.2 Grade separated interchanges	23
3.3 At grade intersections	23
3.4 Alternative options considered in the design	25
3.5 Arterial standard service roads and access roads	28
3.6 Motorway standard access strategy	30
<b>4. Road design</b>	<b>32</b>
4.1 Design standards	32
4.2 Design life	32
4.3 Highway design	33
4.4 Service road and access road design	39
<b>5. Community consultation</b>	<b>42</b>
5.1 Issues outstanding from route selection stage	42
5.2 Issues raised following the preferred route display	44
5.3 Emergency services and state forests consultation on access	51

---

<b>6.</b>	<b>Existing traffic and road infrastructure</b>	<b>52</b>
6.1	Review of existing alignment	52
6.2	Existing highway access	55
6.3	Existing provision for pedestrians and cyclists	55
6.4	Existing public transport network	55
6.5	Existing highway traffic	57
6.6	Existing crash history	59
6.7	Reuse of existing infrastructure	63
<b>7.</b>	<b>Traffic, cyclists, pedestrians and buses</b>	<b>64</b>
7.1	Traffic assignment	64
7.2	Operational performance	64
7.3	Intersection performance	65
7.4	Distance and travel time savings	66
7.5	Crash analysis	67
7.6	Provision for heavy vehicles	68
7.7	Provision for pedestrians	68
7.8	Provisions for cyclists	68
7.9	Provision for public transport	69
<b>8.</b>	<b>Lighting</b>	<b>71</b>
<b>9.</b>	<b>Structures</b>	<b>72</b>
9.1	Cross section requirements for bridges	72
9.2	Existing structures	73
9.3	Bridges	74
9.4	Range Road structure	74
9.5	Design assumptions	75
9.6	Existing structures to be retained	76
<b>10.</b>	<b>Drainage</b>	<b>78</b>
10.1	Design flood immunity	78
10.2	Cross drainage design	79
10.3	Corindi River floodplain	84
10.4	Other structures	89
10.5	Fauna passage design in cross drainage structures	89
10.6	Fish passage	89
10.7	Scour protection	90
10.8	Longitudinal drainage	90

---

10.9	Sub-surface drainage	91
<b>11.</b>	<b>Pavements</b>	<b>93</b>
11.1	Pavement design	93
11.2	Traffic volumes	93
11.3	Pavement design assumptions	93
11.4	Preliminary pavement design	94
11.5	Whole of life pavement analysis	96
11.6	Conclusion	97
<b>12.</b>	<b>Earthworks</b>	<b>98</b>
12.1	Risk	98
12.2	Cuttings	98
12.3	Embankments	99
12.4	Bridges	99
12.5	Quantities	100
12.6	Soft soils	101
12.7	Acid sulfate soils	101
12.8	Contaminated soils	101
<b>13.</b>	<b>Urban design</b>	<b>102</b>
13.1	Study area	102
13.2	Urban and regional design framework	102
13.3	Areas of aesthetic significance	103
13.4	Proposed landscaping treatment	103
13.5	Proposed bridge treatments	103
13.6	Specific urban and regional design treatments	104
13.7	Conclusion	104
<b>14.</b>	<b>Public utilities</b>	<b>105</b>
14.1	Existing utilities	105
14.2	Utilities impacted by the project	105
<b>15.</b>	<b>Signage, linemarking and barriers</b>	<b>109</b>
15.1	Barriers	109
15.2	Signposting policies	109
15.3	Linemarking Designs	109
<b>16.</b>	<b>Terrestrial ecology</b>	<b>110</b>

---

16.1	Field investigations	110
16.2	Potential impacts during construction	111
16.3	Potential impacts during operation	111
16.4	Recommended terrestrial flora and fauna mitigation measures prior to and during construction	112
16.5	Indicative terrestrial flora and fauna management measures during operation	113
<b>17.</b>	<b>Aquatic ecology</b>	<b>119</b>
17.1	Field investigations	119
17.2	Impacts during construction	119
17.3	Impacts during operation	120
17.4	Recommended aquatic flora and fauna mitigation measures during construction	120
17.5	Recommended aquatic flora and fauna mitigation measures during operation	120
<b>18.</b>	<b>Noise</b>	<b>122</b>
18.1	Noise goals	122
18.2	Noise impacted residences	123
18.3	Recommended noise mitigation measures	124
<b>19.</b>	<b>Indigenous heritage</b>	<b>125</b>
19.1	Engagement of Aboriginal stakeholders	125
19.2	Impacts on matters of indigenous heritage	126
19.3	Proposed management measures	131
<b>20.</b>	<b>Non-indigenous heritage</b>	<b>132</b>
20.1	Fieldwork	132
20.2	Impacts on matters of non-indigenous heritage	132
20.3	Indicative management measures	135
<b>21.</b>	<b>Water quality</b>	<b>136</b>
21.1	Potential impacts during construction	136
21.2	Indicative mitigation measures during construction	136
21.3	Potential impacts during operation	140
21.4	Indicative mitigation measures during operation	140
<b>22.</b>	<b>Property boundary adjustments</b>	<b>144</b>
22.1	Determining the road boundary	144
22.2	Land acquisition process	145
22.3	Acquisition requirement	145

---



22.4	Mitigation measures	148
<b>23.</b>	<b>Constructability and staging</b>	<b>149</b>
23.1	Constructability	149
23.2	Staging of the project	152
<b>24.</b>	<b>Construction resources</b>	<b>154</b>
24.1	Material requirements for the upgrade	154
24.2	Material sources	156
24.3	Environmental approvals	158
24.4	Site access and supply routes	159
<b>25.</b>	<b>Temporary infrastructure</b>	<b>160</b>
25.1	Temporary infrastructure requirements	161
25.2	Potential locations	163
25.3	Proposed environmental controls	167
<b>26.</b>	<b>Road user delay management</b>	<b>175</b>
26.1	Southern stage	175
26.2	Northern stage	176
<b>27.</b>	<b>Stage 2 road safety audit</b>	<b>177</b>
27.1	Road safety audit findings and design team response	177
<b>28.</b>	<b>Occupational health and safety</b>	<b>178</b>
28.1	Risk assessment activities	179
<b>29.</b>	<b>Actions arising from value engineering workshop</b>	<b>181</b>
<b>30.</b>	<b>Outstanding issues</b>	<b>184</b>
30.1	Previous outstanding issues	184
30.2	Remaining outstanding issues	186

## Table index

Table 1-1	Overview of project methodology	6
Table 2-1	Project sections	20
Table 3-1	At-grade intersections location and treatment	24
Table 3-2	Non conformances of existing highway north of Wells Crossing	26
Table 4-1	Asset design lives	33
Table 4-2	Engineering design criteria	34

Table 4-3	Summary of departures from desirable horizontal curve requirements	36
Table 4-4	Emergency u-turn bays, public u-turn bays and median crossovers	39
Table 4-5	Service road and access road design criteria	40
Table 5-1	Response to outstanding issues from the route selection stage	42
Table 5-2	Response to issues raised following the preferred route display	44
Table 6-1	Existing bridges in Section B	53
Table 6-2	Existing bridge widths	54
Table 6-3	Access along existing highway	55
Table 6-4	Busways services	55
Table 6-5	Annual Average Daily Traffic (vehicles per day) along the highway from tube counts (29/11/04 – 5/12/04)	57
Table 6-6	Existing highway - travel time (free flow conditions)	58
Table 6-7	Reuse of the existing highway asset	63
Table 7-1	Upgraded Pacific Highway - projected average annual daily traffic	64
Table 7-2	Upgraded Pacific Highway - level of service (HCS 2000)	65
Table 7-3	Upgraded Pacific Highway - distance savings	67
Table 7-4	Existing and upgraded Pacific Highway - travel times	67
Table 7-5	Expected crash reduction - Pacific Highway – Woolgoolga to Wells Crossing	68
Table 8-1	Summary of lighting levels for at-grade intersections	71
Table 9-1	Indicative bridges	74
Table 10-1	Data source and comments	79
Table 10-2	DRAINS parameters	80
Table 10-3	Bridge details and existing flow area	81
Table 10-4	Existing and indicative waterway crossings	82
Table 10-5	Peak design flows on the Corindi River at the upstream boundary of the investigation area	85
Table 10-6	Preliminary culvert and bridge arrangements	87
Table 10-7	Water surface levels at the upstream faces of the proposed bridges on Corindi Floodplain (mAHD)	88
Table 11-1	Traffic summary	94
Table 11-2	Results of whole of life pavement type comparison	97
Table 12-1	Summary of preliminary bridge foundation types	100
Table 13-1	Areas of aesthetic significance	103
Table 14-1	Major utilities within the study area	105
Table 14-2	Telstra utilities impacted by the proposed alignment	105
Table 14-3	Country Energy utilities impacted by the proposed alignment	107
Table 16-1	Indicative fauna underpass structures	114



Table 16-2	Indicative proposed fauna and cattle fencing	118
Table 21-1	Preliminary sediment basin sizing	137
Table 21-2	Indicative water quality basin size and location	141
Table 22-1	Acquisition requirements for Class A upgrade	145
Table 24-1	Material requirements	154
Table 24-2	Identified quarries, materials and reserves	156
Table 25-1	Temporary infrastructure location suitability	165
Table 25-2	Potential environmental impacts and mitigation measures	169
Table 27-1	Summary of major road safety audit findings	177
Table 28-1	The 'Hierarchy of Controls'	179
Table 29-1	Summary of actions arising from value engineering workshop	181
Table 30-1	Previous issues raised during the 20 per cent Concept Design Review Workshop and their resolutions	184

## Figure index

Figure 1	Location of the preferred route	3
Figure 2	Project sections	11
Figure 3	Route options	14
Figure 4a	Preferred route corridor May 2007	18
Figure 4b	Refind preferred route corridor	19
Figure 5	Crash locations	61
Figure 6	NSW Coastline Cycleway (Coffs Harbour City Council and Clarence Valley Council)	70
Figure 7	Culturally sensitive areas	129
Figure 8	Location of known Aboriginal heritage items	130
Figure 9	Locations of items of non-indigenous heritage significance	133

## Appendices

A	Design Checklist
B	Range Road Overpass – Options Considered and Construction Staging
C	Minutes of community meeting